

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 21  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 3, 1878, under GLO contract No. 293, as follows:

Set a stone, 18" x 12" x 5", on level for the corner to sections 13, 14, 23 and 24. Dug pits and drove a pine stake.



Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 23" x 11" x 6" and is plainly marked with 3 notches on the north edge and one notch on the east edge. The original pine stake is gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 23" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the northwest side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636, 13", attached at ground level, bears N58° 30'E, 162.5 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636, 24", attached at ground level, bears S43° 30'E, 113.6 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636, 23", attached at ground level, bears S33°W, 50.6 feet.

A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer, marked "PLS 1636, 14", attached at ground level, bears N68° 30'W, 97.2 feet.

A 5 foot steel fence post with a "Witness Post" sign attached bears East, 2.0 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 5, 2000. Magnetic declination set in compass: 18°E.

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: 10/17/2000

*David H. K. ...*

RECEIVED BY  
Umatilla County Surveyor  
Date 10-00  
Exp'd by KR  
No. 00-214-R

RECEIVED BY  
Umatilla County Surveyor  
Date  
No.