

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 9
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 7, 1878, under GLO contract No. 293, as follows:

Set a stone, 12" x 10" x 8", for corner to sections 16, 17, 20 and 21. Dug pits and drove a willow stake as per instructions

T2S R30E
S17|S16
S20|S21
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 13" x 10" x 8" and is plainly marked with four notches on one (east) edge and three notches on another (north) edge. The stake and pits of record are gone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the iron pipe is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 16", attached at ground level, bears N29° E, 106.3 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 21", attached at ground level, bears S24° 30' E, 133.9 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 20", attached at ground level, bears S4° 30' W, 131.1 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 17", attached at ground level, bears N60° W, 109.8 feet.

The two reference monuments to the south are south of a gully.

I nail a "witness post" sign to a wooden fence post one foot southwest of the corner.

I hereby certify the above corner point was perpetuated as hereon described on February 6, 2002. Magnetic declination set in compass: 16° E.


REGISTERED
PROFESSIONAL
LAND SURVEYOR
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636
Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 2-02
Rec'd by KR
No. 02-31-R