

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R - 23
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 3, 1878, under GLO contract No. 293, as follows:

Set a stone, 14" x 8" x 6", for the 1/4 section corner.

T2S R30E
1/4 S 24
S 25
PLS 1636
2000

Original corner evidence recovered:

Found the original corner stone solidly set 10" in the ground. The corner stone is 16" x 12" x 6" and is plainly marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" galvanized iron pipe 23" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N29°E, 88.5 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S27°E, 79.0 feet.

A 5/8" x 36" iron rod, set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S55° 15'W, 99.1 feet.

A 5/8" x 36" iron rod, set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 NW" attached at ground level, bears N25° 30'W, 125.6 feet.

A 5 foot steel fence post with a "Witness Post" sign attached bears West, 2.0 feet.

A farm road projecting NNE and SSW bears East, 30 feet.

I hereby certify the above corner point was perpetuated as hereon described on October 5, 2000. Magnetic declination set in compass: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: 10/17/2000

David H. Klein

RECEIVED BY
Umatilla County Surveyor
Date 10-00
Rec'd By KR
No. 00-218-R