

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 15
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin on September 5, 1878, under GLO contract No. 293, as follows:

Set stone, 24" x 10" x 8", for 1/4 section corner.

T2S R30E
1/4 S27
S34
PLS 1636
2002

Original corner evidence recovered:

Found the original corner stone solidly set in a small mound of stones. Corner stone is 25" x 10" x 6" and is marked "1/4" on the south face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 19" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N37° E, 74.7 feet.

A 5/8" x 24" iron rod set 16" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S22° E, 59.3 feet.

A 5/8" x 24" iron rod set 20" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S31° 30' W, 77.2 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N19° 30' W, 54.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on January 28, 2002. Magnetic declination set in compass: 18° E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on: _____

RECEIVED BY
Umatilla County Surveyor
Date 2-02
Rec'd by KK
No. 02-38-R