


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**N - 25
DIAGRAM**

History of original corner establishment:

The original corner was established on October 21, 1871, by George S. Pershin and George Williams under their joint GLO contract No.154, as follows:



Set stone, 22" x 7" x 5", for corner to sections 13, 24, 18 and 19, on a southwest hillside.

Subsequens subdivision of T30 1/2E changed this corner to the corner for sections 13 and 24, R30E, and sections 14 and 23, R30 1/2E.

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 22" x 11" x 6" and is tapered to a point. The stone is marked with 3 notches on one edge on the fat end of the stone.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 17" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone to the east of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N72°E, 92.6 feet.


A 5/8" x 24" iron rod, set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S40° 30'E, 75.5 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S71°W, 111.2 feet.

A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N20° 30'W, 72.1 feet to the top of the rod, which is leaning northeast.

A 5 foot steel fence post with a "Witness Post" sign attached bears south, 1.0 foot.

I hereby certify the above corner point was perpetuated as hereon described on June 13, 2000. Magnetic declination set in compass: 18°E.



Dennis L. Gaylord

Renews June 30, 2001

RECEIVED BY
 Umatilla County Surveyor
 Date 6-2000
 Rec'd By RF
 No. 00-131-R

Recorded at the office of County Surveyor, Umatilla County, State of Oregon, on: