

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 23
DIAGRAM

History of original corner establishment:

The original corner was established on December 27, 1878, by George S. Pershin under GLO contract No. 313, as follows:

Set a stone, 15" x 10" x 10", on a southwest slope in a mound of stones for the 1/4 section corner.

T2S R30 1/2E
1/4 S13
S 24
PLS 1636
2000

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The original corner stone is 17" x 11" x 10" and is marked "1/4".

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 14" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I place the corner stone to the east of the iron pipe and build a mound of stones around the pipe and corner stone, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N30°E, 126.4 feet.

A "UECA" power pole, with numbers "2S 30.5E 135000" on a metal sign attached to the pole, bears S74°E, 104.8 feet. I nail a 3/4" brass washer, marked "PLS 1636", to the pole one foot above the ground, and a "Bearing Object" sign on the pole, both facing the corner.

A 5/8" x 24" iron rod set 24" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S43° 30'W, 147.2 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N52° 30'W, 105.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on June 13, 2000. Magnetic declination set in compass: 18°E.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-2000
Rec'd By KR
No. 00-130-R