


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J - 9  
DIAGRAM

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 21, 1864, under GLO contract No. 107, as follows:

Set stone for corner to sections 8, 9, 16 & 17. (The size of the stone is not given in the original field notes).



Corner evidence recovered:

The original corner stone is loosely set in a small mound of stones. The corner stone is 14" x 11" x 10" and is plainly marked with four notches on the east edge and two notches on the north edge.

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 28" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S9", attached at ground level bears N74°30'E, 98.3 feet.  
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S16", attached at ground level bears S43°30'E, 87.7 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S17", attached at ground level bears S55°W, 104.9 feet. This reference is southwest of a small draw.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 S8", attached at ground level bears N58°30'W, 130.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 16, 1998. Magnetic declination: 18°E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Dennis L. Gaylord*  
OREGON  
JULY 16, 1978  
DENNIS L. GAYLORD  
1636

Renews June 30, 1999.

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1998.

RECEIVED BY  
Umatilla County Surveyor  
Date 4-98  
Rec'd By RR  
No. 98-632