

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L - 9  
DIAGRAM

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 21, 1864, under GLO contract No. 107, as follows:

Set stone 18" x 12" x 8" for 1/4 section corner.

T2S R31E  
1/4  
S17;S16  
PLS 1636  
1998

Corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 21" x 14" x 7" and is plainly marked "1/4".

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 25" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the southwest side of the iron pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod set 19" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N31°E, 106.1 feet.  
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S48°E, 86.9 feet.  
A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S49°15'W, 210.9 feet. This reference is southwest of a small draw.  
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N43°W, 77.3 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 16, 1998. Magnetic declination: 18° E.



Renews June 30, 1999.

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 1998.

RECEIVED BY

Umatilla County Surveyor  
Date 4-98  
Rec'd By KK  
No. 98-64-X