


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 19

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:

Set a stone 24" x 12" x 8" for the 1/4 section corner.



Description of corner evidence found:

The original corner stone is loosely set in a small mound of stones. The stone is 24" x 12" x 7" and is marked "1/4".



Description of monument and accessories established to perpetuate the original location of this corner:

At the point occupied by the original corner stone, I set a 1" x 30" iron pipe, 18" into the ground to bed rock. I bury the corner stone along the northwest side of the pipe and build a mound of stones around the pipe to the cap. A 2 1/2" brass cap attached is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 NE", bears N47°E, 100.9 feet.
- A 5/8" x 24" iron rod, set 23" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 SE", bears S47°E, 106.1 feet.
- A 5/8" x 36" iron rod, set 35" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 SW", bears S37°W, 116.0 feet.
- A PP&L power pole, with numbers "122" attached 5 feet above the ground; a 3/4" brass washer, marked "PLS 1636", attached one foot above the ground, and a bearing tree sign nailed 5 feet above the ground, bears N13°W, 146.4 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 26, 1998. Magnetic declination: 20°E.

Office of COUNTY SURVEYOR County of UMATILLA
State of OREGON, I hereby certify that the within instrument was filed in this office
for record on the 5 day of March, 1998
Dennis L. Gaylord by _____
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 3-98
Rec'd By [Signature]
No. 98-25-R