


History of original corner establishment:

The original corner was established by Daniel Chaplin on November 19, 1864, under GLO contract No. 107, as follows:  
Set stone 18" x 12" x 8" for 1/4 section corner.



Description of corner evidence found:

The original corner stone is solidly set, protruding 10" above the ground, and plainly marked "1/4" on the west face. The stone is 15" x 12" x 8".

Description of monument and accessories established to perpetuate the original location of this corner:

In the exact position occupied by the corner stone, I set a 1 1/2" x 30" iron pipe 26" into the ground. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached is marked as shown in the diagram above, from which:

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S35 NE" bears N41 3/4 E, 110.4 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S35 SE" bears S28 1/2 E, 70.2 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S34 SW" bears S55 1/2 W, 94.8 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer attached at ground level marked "PLS 1636 S34 NW" bears N31 1/2 W, 79.5 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 9, 1997. Magnetic declination: 20 E.

REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON  
JULY 14, 19  
DENNIS L. GAYLORD  
1636

Office of... County of...  
State of... I hereby certify that the within instrument was filed in this office for record on the 29 day of February, 1997  
David H. [Signature] by [Signature] (DEPUTY)  
(COUNTY OFFICIAL)

RECEIVED BY  
Umatilla County Surveyor  
Date 2-97  
Rec'd By KH  
No. 97-18-R