

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 9
DIAGRAM

History of original corner establishment:

The original corner was established by Daniel Chaplin on November 20, 1864, under GLO contract No. 107, as follows:

T2S R31E
1/4
S32|S33
PLS 1636
1998

Set stone 18" x 8" x 8" for 1/4 section corner.

Corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. The corner stone is 17" x 11" x 8" and is plainly marked "1/4".

Monument and accessories established to perpetuate the original location of this corner:

In place of the original corner stone, I set a 1" x 30" iron pipe, 23" into the ground. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the east side of the iron pipe and build a mound of stones around the pipe to the cap, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level bears N43°30'E, 121.5 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level bears S42°E, 140.0 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level bears S71°30'W, 128.9 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level bears N47°W, 144.6 feet.

I hereby certify the above corner point was perpetuated as hereon described on April 4, 1998. Magnetic declination: 18°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylor
C. S. N.
DENNIS L. GAYLORD
1636

Renews June 30, 1999

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1998.

RECEIVED BY
Umatilla County Surveyor
Date 4-78
Rec'd By KR
No. 98-622