

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 17
DIAGRAM

History of original corner establishment:

The original corner was established by John C. Arnold on September 30, 1891, under GLO contract No. 551, as follows:

T2S R32E
S27 | S26
S34 | S35
PLS 1636
1999

Set a basalt stone, 12" x 12" x 8", 8" into the ground, marked with one notch on the south and 2 on the east edges, in a mound of stones, from which:

- A 14" pine bears N85°W, 53 links (34.98 feet).
- A 38" pine bears S1°E, 135 links (89.1 feet).

Corner evidence recovered:

Found the original corner stone solidly set in a mound of stones. The corner stone is 12" x 11" x 7" and is marked with one groove on the south face and two notches on the east edge, from which:

A sawn and decayed 36" Ponderosa Pine stump, with scribe marks, "35", visible, bears S1°30'W, 89.1 feet to the scribed face. This stump has an old bearing tree sign attached to it. The original bearing tree to the northwest is gone.

Monument and accessories established to perpetuate the original location of this corner.

In place of the original corner stone, I set a 1" x 30" iron pipe 24" into the ground. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone to the west of the pipe and build a mound of stones around the pipe to the cap, from which:

- A 21" Douglas-fir, scribed "T2S R32E S26 BT", bears N65°E, 140.3 feet.
- A 14" Ponderosa Pine, scribed "T2S R32E S35 BT", bears S9°E, 67.1 feet.
- A 14" Ponderosa Pine, scribed "T2S R32E S34 BT", bears S52°30'W, 43.1 feet. This tree has a "Witness Post" sign attached to the back.
- A 15" Ponderosa Pine, scribed "T2S R32E S27 BT", bears N82°W, 136.7 feet. This tree has a "Witness Post" sign attached to the back.

The four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "E", and have a "Bearing Object" sign nailed above the blazes.

I hereby certify the above corner point was perpetuated as hereon described on October 2, 1999. Magnetic declination: 19°E.

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on 12 Oct, 1999.

RECEIVED BY
 Umatilla County Surveyor
 Date 10-99
 Rec'd By KK
 No. 99-212-R