

Index

File No. V-25

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. Sec.

T 2S R. 32E


R.D. Ukiah County _____

Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

At corner position found 18"x11"x7" stone with 5 notches on north edge & 1 notch on south edge 3" in ground with remains of stone mound partially around stone and partially slid downhill.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

No bearing trees were set.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner falls on a steep west slope approx. 75' west of old jeep trail.

Signature

Handwritten Signature

Title

Division

Headquarters

Date

ORLS

1294


9-77

7100-52-(3-68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

In place of stone set 2 1/2"x30" galvanized pipe with brass cap stamped:



Set pipe 20" in ground with mound of stone to cap and buried original stone alongside.

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

A Douglas Fir 14" dia. bears N46⁰W, 24.2 ft, scribed T2S R32E S25 BT.

A Douglas Fir 9" dia. bears S28⁰E, 58.2 ft, scribed T2S R32E S36 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red. Attached 54-4 sign to metal post 5' south of corner.

Work Done By R. C. Orton Title Party Chief Date 7-31-80 State Registration No. _____
or Agency _____

Certified Cor. Record Prepared? (Yes) No Filed At: _____ Date _____

REMARKS

Witnesses: R. Orton
L. Huntsman
D. Allen