

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 13
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on October 9, 1864, under GLO contract No. 106, as follows:
Set stone, 16" x 12" x 5", for corner to sections 3, 4, 33 and 34.



On May 27, 1882, George S. Pershin searched for Thompson's corner, but did not find it. Pershin set a new corner of minimum control, under GLO contract No. 430, as follows:
Set a basalt stone, 18" x 8" x 6", 12" into the ground, on a southwest slope, marked with 3 notches on the east and west edges, from which:
A 36" pine bears N28°E, 102 links (67.32 feet).
A 16" pine bears N22°W, 70 links (46.2 feet).

On October 2, 1891, under GLO contract No. 551, John C. Arnold recovered a mound of stones at the corner. Arnold set a basalt stone, 12" x 10" x 5", marked with 3 notches on the east and west edges, in the recovered mound of stones, from which:
A 23" pine bears S10°W, 30 links (19.8 feet).
A 32" pine bears S40°E, 90 links (59.4 feet).


Corner evidence recovered:

Found the original Arnold corner stone loosely set in a mound of stones. The corner stone is 14" x 11" x 5" and is plainly marked with 3 notches on the east and west edges, from which:
A broken and decayed 24" Ponderosa Pine stump with scribes "BT" visible bears S 9°W, 19.8 feet.
A sawn and decayed 36" Ponderosa Pine stump, no marks remaining, bears S52°E, 59.4 feet.

Monument and accessories established to perpetuate the original position of this corner:

At the point occupied by the corner stone, I set a 1" x 30" iron pipe, 18" into the ground surrounded by a mound of stones to the cap. A 2 1/2" brass cap attached is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe, from which:
A 23" Ponderosa Pine, scribed "T2S R32E S34 BT", bears N4°E, 8.9 feet. This tree has a "Bearing Object" sign nailed to the back.
A 15" Ponderosa Pine, scribed "T3S BT", bears S31°E, 121.8 feet.
A 8" Ponderosa Pine, scribed "S2 BT", bears S72°W, 63.2 feet.
A 25" Ponderosa Pine, scribed "T2S R32E S33 BT", bears N35°30'W, 62.7 feet. All four new bearing trees are scribed on double blazes, have a 3/4" brass washer, marked "PLS 1636", nailed flush to the scribed "B", and have a "Bearing Object" sign nailed above the blazes. The original bearing tree stumps have "Bearing Object" signs nailed to them.

I hereby certify the above corner point was perpetuated as hereon described on July 18, 1999. Magnetic declination: 18°E.


Dennis L. Gaylord

Renews June 30, 2001
Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1999.

RECEIVED BY

Umatilla County Surveyor
Date 8-99
Rec'd By JK
No. 99-136-R