

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 19  
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on October 9, 1864, under GLO contract No. 106, as follows:

T2S R32E  
1/4 S35  
T3S R32E  
1988  
OPLS 644

Set stone 18" x 12" x 4" for 1/4 section corner.

On May 27, 1882, George S. Pershin, under GLO contract No. 430, searched for the Thompson corners along the township line, but failed to recover enough corners to define the location of the Thompson line. Pershin set new corners along the township line. At this corner, Pershin set:  
A basalt stone, 14" x 8" x 6", 10" into the ground on a northwest slope, marked "1/4" on the north face, from which:  
A 10" Larch bears N18°W, 5 links (3.3 feet), marked "1/4 S BT".  
A 13" Larch bears south, 9 links (5.94 feet), marked "1/4 S BT".

On August 24, 1988, Duane I. Griffith recovered Pershin's corner as follows:

Found stone, 14" x 10" x 5" set 7" in the ground marked "1/4" on the north face, from which:  
A 18" Tamarack bears south, 9 links. This tree is cut off about 6 feet high, with scribing visible. Distance is to blazed face of tree.  
A root hole bears N18°W, 5 links.  
Griffith set a 2 1/2" x 30" aluminum pipe with an aluminum cap marked "Bagett Griffith & assoc." and as shown in the diagram above. The pipe is set 28" into the ground, and the corner stone is buried to the southwest of the pipe, from which:  
A 10" Douglas-fir bears N22°E, 70.24 feet and is scribed "1/4 S35 BT".  
A 5" Lodgepole Pine bears N60°W, 15.3 feet and is scribed "X BT".  
A 6' steel fence post with a land survey monument sign attached, bears east, 3.93 feet.

Corner evidence recovered:

I found the Griffith monument and accessories as described above. I also recovered the original corner stone set by Thompson in 1864, as follows:  
The Thompson corner stone is loosely set, but appears undisturbed. The stone is 17" x 11" x 6" and is plainly marked "1/4" on one face. This stone is approximately S70°W, 160 feet from the Griffith monument. These two points are not intervisible, and this bearing and distance was determined using resource grade GPS, which is generally accurate to plus or minus 1 meter.

Description of steps taken to perpetuate the original location of this corner:

I perpetuate the original location of the Thompson corner by setting in it's place a 5/8" x 24" iron rod, 12" into the ground. A 1 1/2" aluminum cap attached is marked "LS 1636". I build a mound of stones around the rod and the original corner stone, which is to the northeast of the rod.

I hereby certify the above corner point was perpetuated as hereon described on October 2, 1999.



Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on 15 October, 1999.

RECEIVED BY

Umatilla County Surveyor  
Date 10-99  
Rec'd By XR  
No. 99-216-2