

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 9
DIAGRAM

History of original corner establishment:

The original corner was established by David P. Thompson on October 9, 1864, under GLO contract No. 106, as follows:
Set stone 20" x 12" x 10" for corner to sections 32, 33, 4 and 5.

T2S | R32E
S32 | S33
S3
T3S R32E
PLS 1636
1999

On May 27, 1882, George S. Pershin, under GLO contract No. 430, ran a new township line, superseding the one established by Thompson, as follows: A point 96 links (63.36 feet) north of the old corner, which is a stone marked with 4 notches on east edge, set a stone, basalt, 18" x 14" x 4", in a mound of stone on south slope near top of hill for corner to sections 32 and 33 marked with 2 notches on west and 4 notches on east edges.

On October 3, 1891, John C. Arnold, under GLO contract No. 551, recovered the following: At corner 4, 5, 32, 33, a basalt stone in a mound of stone marked with 4 notches on east and 2 notches on west edges.

Corner evidence recovered:

Found Pershin's corner stone loosely set in a mound of stones. The corner stone is 20" x 15" x 4" and is faintly marked with 4 small notches on the east and 2 small notches on the west edges, from which: Thompson's original corner stone is solidly set in a mound of stones. This stone is 24" x 17" x 13" and is plainly marked with 4 notches on the east edge and 2 notches on the west edge. From the Pershin corner, this stone bears S1°E, 63.4 feet. A very old fence line projects east and west from this stone. Nothing remains of this fence other than a row of stone mound rock jacks and decayed fence posts. A barbed wire fence projecting east and west is about 300 feet south.

Monument and accessories established to perpetuate the original position of this corner:

At the position occupied by the Pershin corner stone, I set a 1" x 30" iron pipe 15" into the ground to bedrock. A 2 1/2" brass cap attached to the pipe is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe to the cap, from which:
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 S33", attached at ground level, bears N51°E, 106.7 feet.
A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S41°15'E, 111.5 feet.
A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S35°30'W, 101.0 feet.
A 5/8" x 24" iron rod set 14" into the ground, surrounded by a mound of stones, with a 3/4" brass washer, marked "PLS 1636 S32", attached at ground level, bears N56°15'W, 102.7 feet.

I hereby certify the above corner point was perpetuated as hereon described on August 24, 1999. Magnetic declination: 18° E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Dennis L. Gaylor

OREGON
JULY 14, 1978
DENNIS L. GAYLORD

Renews June 30, 2001

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on _____, 1999

Umatilla County Surveyor
Date 7-99
Rec'd By KK
No. 99-146-R