


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. V-3

History of original corner establishment:

In 1890, under G.L.O. contract No. 551, John C. Arnold set a basalt stone 20x6x5 ins. 15 ins. in the ground & marked 1/4 on the north face and raised a mound of stones 2 ft high & 4 1/2 ft wide over the stone from which he marked:

A Pine 20" dia. bears S82°40'E 178 lks (117.48 ft) scribed 1/4S BT. A Pine 24" dia. bears N59°E 148 lks (97.68 ft) scribed 1/4S BT.



Description of corner evidence found:

Found: An old logged Ponderosa Pine stump well decayed with BT scar laying on the ground at the base for SE BT.

Found: An old rotted Ponderosa Pine snag with BT blaze at foot. Snag had been opened with axe to lower part of the blaze revealing no scribing for NE BT. At intersection of record dist's. found stone mound, but was unable to find original stone after a diligent search.

Description of monument and accessories I established to perpetuate the original location of this corner:

At intersection of record dist's. from original BT's set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set pipe 24" in ground with mound of stone to cap.

Bearing Trees:


Old: A Pine stump bears S85°E 117.48 ft.

A Pine snag bears N49°E 97.68 ft.

New: A 19" Douglas Fir bears S8°E 33.8 ft, scribed 1/4 S31 BT.

A 12" dia. Douglas Fir bears N39°E 66.2 ft, scribed 1/4 S30 BT.

Attached 54-3 & 54-4 signs to all BT's. Attached brass washer stamped LS1294 to foot blaze of new BT's. Painted blazes and 6" band around all BT's. Attached 54-4 sign to metal post 5' east of corner.



I hereby certify the above corner monument was re-established as herein described on August 19, 1980.

Witnesses: R. Orton
G. Wagoner
G. Lester
J. Anderson



Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of..... December....., 19.....80
..... David..... by..... Deputy.....
(COUNTY OFFICIAL) (DEPUTY)