

Index

File No. V-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____

Cor. 1/4
No. _____


T 2 S R. 33E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Could find no evidence of the original stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Found: An old logged Ponderosa Pine stump well decayed with BT scar laying on the ground at the base for SE BT. Found: An old rotted Ponderosa Pine snag with BT Blaze at foot. Snag had been opened with axe to lower part of the blaze revealing no scribing for NE BT.

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

The corner falls on a steep west slope about 200' East of Pearson Creek Road and 150' east of Pearson Creek.

Signature

Title

Division

Headquarters

Date

ORLS

1294

9-77

7100-52-(3-68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At intersection of record dist's. from original BT's, set
2/1/2"x30" galvanized pipe with brass cap stamped:

T2S R33E
1 S30
4 S31
1980
OR PLS 1294

Set pipe 24" in ground with mound of stone to cap.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Bearing Trees:

Old: A Pine stump bears S85°E 117.48 ft.

A Pine snag bears N49°E 97.68 ft.

New: A 19" Douglas Fir bears S8°E 33.8 ft, scribed 1/4 S31 BT.

A 12" dia. Douglas Fir bears N39°E 66.2 ft, scribed 1/4 S30 BT.

Attached 54-3 & 54-4 signs to all BT's. Attached brass washer stamped LS1294
to foot blaze of new BT's. Painted blazes and 6" band around all BT's. Attached
54-4 sign to metal post 5' east of corner.

Work Done By R. C. Orton Title Party Chief Date 8-19-80 State Registration No. _____
or Agency _____

Certified Cor. Record Prepared ? (Yes) No Filed At: _____ Date _____

Witnesses:

REMARKS

R. Orton
G. Wagoner
G. Lester
J. Anderson

Index File No.

V-3

T.

25

R.

33E

M.

Tract or Surv. No.

Cor.

12

13