

Index

File No. X-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_ Cor. No. C 1/4


T 2S R. 33E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

No corner was originally set.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls on a slight east slope in a stand of Firs about 350' west of Pearson Creek Road.

*Signature*

Title

Division

Headquarters

Date

7100-52-(3/68)

ORLS

1294


9-77

5

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:



Set pipe 15" in ground with mound of stone to cap.

**ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Bearing Trees:

A Douglas Fir 12" in dia. bears N18<sup>0</sup>E 7.0 ft, scribed C 1/4 S31 BT.

A Douglas Fir 11" in dia. bears S74<sup>0</sup>E 12.5 ft, scribed C 1/4 S31 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's Red.

Attached 54-2 & 54-4 signs to metal post 5' south of corner. Attached 54-2 & 54-9 signs to metal post 5' west of corner.

Work Done By R. C. Orton Title Party Chief Date 8-21-80 State Registration No. \_\_\_\_\_  
or Agency \_\_\_\_\_

Certified Cor. Record Prepared? (Yes)  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

Witnesses:	R. Orton	REMARKS
	G. Wagoner	
	G. Lester	
	J. Anderson	

Index File No.      T.      R.      M.      Tract or Surv. No.      Cor.

X-3      25      33E

9  
10  
11  
12  
13