


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. X-5

History of original corner establishment:

In 1890, under G.L.O. contract No. 551, John C. Arnold set a basalt stone 16x7x5 ins, 6 ins. in ground (Digging impractical) for 1/4 cor. to S31 & S32. Marked 1/4 on the west face and raised a mound of stones 1 1/2 ft. by 3 1/2 ft over corner. (Pits imprac.)




Description of corner evidence found:

A diligent search was made and the original corner stone could not be found.

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2"x30" galvanized pipe with bass cap stamped:
Set pipe 14" in ground with mound of stone to cap.



Trees for BT's and steepness of hillside makes it imprac. to build mounds of stone for Bearing Objects, so Bearings were turned to distinguishing land marks.

Bearing Objects:

S78°E a large Lone Fir on a bald hillside slope to the west at the head of a east-west draw.
S23°E to a rock point on the skyline of an east-west ridge. Ridge is mostly covered by trees. Rock point sets out in a clearing. Bearing shot to highest point.



I hereby certify the above corner monument was established as herein described on August 18, 1980.

Witnesses: R. Orton
G. Wagoner
G. Lester
J. Anderson

Office of..... County Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of..... December....., 19 80
David Hammelein, by Betty Spatta
(COUNTY OFFICIAL) (DEPUTY)