


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. Z-(1-2)

History of original corner establishment:

No corner was originally set.



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set pipe 15" in ground with mound of stone to cap.

T2S R33E
 $\frac{1}{16}$ S31 120
 T3S
 1980
 OR PLS 1294

Bearing Trees:

A Ponderosa Pine 20" dia. bears N76°E 267.6 ft, scribed 1/16 120 S31 BT.
A Douglas Fir 10" dia. bears N32°W 160.1 ft, scribed 1/16 120 S31 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's Red. Attached 54-2 & 54-4 signs to metal post 5' east of corner. Attached 54-2 & 54-9 signs to metal post 5' north of corner.

I hereby certify the above corner monument was established as herein described on August 22, 1980.

Witnesses: R. Orton
G. Wagoner
G. Lester
J. Anderson



Office of..... County Surveyor..... County of..... Umatilla
 Oregon
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... December....., 1980
 David Kuntze..... by..... B. Skatts.....
 (COUNTY OFFICIAL)..... (DEPUTY)