

USDA-FOREST SERVICE

Index File No. Z-1

**CORNER RECORD (SEARCH)**  
(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_

Cor. No. 1/16 80

T 2S R. 33 E

R.D. Ukiah


County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

No Corner was originally set.

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner falls on a steep east slope approx. 50' south of E-W fence.

*Signature*  
*Hubert D. ...*

Title

Division  
*ORLS*

Headquarters  
*1294*

Date  
*9-77*

7100-52-(3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

At surveyed point set 2 1/2"x30" galvanized pipe with brass cap stamped:

Set pipe 20" in ground with mound of stone to cap.

T2S R33E  
 1/16 S31 80  
 T3S  
 1980  
 OR ELS 1294

9

**ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Bearing Trees:

A Douglas Fir 9" dia. bears N17<sup>0</sup>E, 8.6 ft, scribed 1/16 S31-80 BT.

A Douglas Fir 9" dia. bears N57<sup>0</sup>W, 19.7 ft, scribed 1/16 S31-80 BT.

Attached 54-3 & 54-4 signs to both BT's. Attached brass washer stamped LS1294 to foot blaze of both BT's. Painted blazes and 6" band around both BT's red. Attached 54-2 & 54-4 signs to metal post 6' north of corner. Attached 54-2 & 54-9 signs to metal post 6' west of corner.

10

Work Done By R. C. Orton Title Party Chief Date 8-25-80 State Registration No. or Agency \_\_\_\_\_

Certified Cor. Record Prepared? (Yes)  No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

11

Witnesses: R. Orton  
 G. Wagoner  
 G. Lester  
 J. Anderson

REMARKS

Index File No. 2-1-80 T. 25 R. 33E M. \_\_\_\_\_ Tract or Surv. No. \_\_\_\_\_ Cor. 13  
 U.S. G.P.O. 1977-725-576/586

12