

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/24/01

CORNER DESIGNATION: T1S R34E, Z-1, The Southwest Corner of Section 31.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Currin and Nolan under Special Contract dated May 4, 1887. Record states: Set basalt stone, 24 x 10 x 8 ins., 18 ins. in ground, for Cor. to Tps. 1 & 2 S., Rs. 33 & 34 E., marked with 6 notches on N., S., W. & E. edges. Raised mound of stone alongside. Pits impracticable. A rock, 10 x 6 x 4 ft. above ground, brs. S.55°E., 125 lks dist.

MONUMENT AND ACCESSORIES FOUND:

Found a 24 x 10 x 8 inch basalt with 6 notches on four sides, lying downhill from a stone mound. With an ancient wood post lying beside it. From the stone mound, a rock, 10 x 6 x 4 foot out of ground, bears S 55° E., 125 links to edge of protruding rock.

MONUMENT MARKING DETAIL:

T1S
R33E R34E
S36|S31
S1 | S6
T2S
2001
PLS 1106

MONUMENT SET:

A position of recovered stone mound, set a 2 1/2" brass cap on 1 1/4 by 30" galv. iron pipe 20" in the ground and rebuilt stone mound around monument. Placed original corner stone in the stone mound on uphill side with notches visible. Mound of stone is 4' in diameter, cap protrudes 4" from stone mound. From the new corner monument:

A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", 4 inches above ground bears N 50° E, 65.8 feet.

"XBO" chiseled on the West face of the 10' x 6' x 4' above ground rock (original accessory), 1' above ground level, bears S 54° E, 83.0 feet.

A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears S 44° W, 54.5 feet.

A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears N 67° W, 19.7 feet.

Wired bearing object signs to the 5/8" iron rebars.

LOCATION AND COMMENTS:

Corner is located on steep hillside East of Lake Creek.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD 83/91, INT. FOOT:

N = 647371.13

E = 8686489.08

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT
Mark Hammersla

\1S34Z1

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY
Umatilla County Surveyor

Date _____

Rec'd By _____

No. 02-45-R