

Index Y-15

File No. _____

T 2S R. 34E

Merid. Willamette

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)


R.D. La Grande County Union

N.F. Wallowa-Whitman State Oregon

Tract or Survey No. _____

Cor. No. 1/16

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. FW 17-172

Filed At. S.O. La Grande

Object Ident. Direct

Ident. By B.B.B. RLS

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Barry B. Barber

Title

P. L. S.

Division

Headquarters

Sumpter

Date

11-4-80

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 12" in the ground and mound of stone around to cap.

T2S R34E
C
S1/16 \updownarrow S34
C
OR PLS 1051
1980

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which by magnetic declination of N20°E: An 11" pine bears N15°W, 30.4 ft. scribed CS1/16S34 BT A 13" pine bears S08°W, 72.6 ft. scribed CS1/16S34 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' east and 54-2 on steel fence post 5' north of the corner.

Work Done By B. B. Barbour Title P.L.S. Date 11-4-80 State Registration No. OR 1051
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor's Date _____

REMARKS

Witnesses: Daniel Rowland
Doug Moser
Ron Gilroy