

Index

File No. Y-16

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. 1/16

T 2S R. 34E

R.D. La Grande


County Union

Merid. Willamette

N.F. Wallowa-Whitman

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None.

PHOTO IDENTIFICATION DATA

Photo No. FWP-17-172

Filed At. S.O. Jakrudo

Object Ident. Direct

Ident. By B.B.B. RLS

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner falls in bottom of small drain about 125' west of road.

Signature

Title

Division

Headquarters

Date

7100-52 (3. 68)

Barry B. Barbour

P, L, S,

Sumpter

11-3-80

CORNER RECORD (PERPETUATION)

MONUMENT : DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

At surveyed point set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

T2S R34E
SE
1/16 S34
OR PLS 1051
1980

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which by magnetic declination of N20°E: A 15" fir bears N66°E, 70.6 ft. scribed SEL/16S34 BT. A 10" fir bears S16°E, 44.9 ft. scribed SEL/16S34 BT. Painted blazes red and 6" red band around. Placed 54-3s, 54-9s and brass washers stamped PLS 1051 on BTs. Placed 54-2 and 54-9 on steel fence post 5' south and 54-2 on steel fence post 5' west of the corner.

Work Done By B. B. Barbour Title P.L.S. Date 11-3-80 State Registration No. or Agency OR 1051

Certified Cor. Record Prepared ? Yes No Filed At: Union County Surveyor's Date _____

REMARKS

Witnesses: Daniel Rowland
Doug Moser
Ron Gilroy