


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1891 by Jacob C. Cooper, unerr General Land Office Contract No. 397.

Surveyor General records (notes) states: Set basalt stone 18x14x5, 8 ins. in the ground and made stone mound 2 ft. high for cor. to sec. 3, 4, 33 & 34.

note: No restoration appears in the county records.



2-13

Description of corner evidence found:

Found a basalt stone 18x14x5 ins. in a mound of stone. The corner stone has obviously been disturbed, however remains of the original mound of stone are present & the section corner location is accepted as the center of the original stone mound.

Description of monument and accessories established to perpetuate the original location of this corner

Set 30"x2 1/2" iron pipe with 3" brass cap marked as shown, 6" in the ground to solid rock & chiseled an "X" in the rock under the pipe for the corner to sections 33, 34, 4 & 3 & raised a mound of stone 5 ft. diam. & 3 ft. high around the pipe.

From which, new Bearing Trees

A Pine 20 ins. diam. bears N47°E 81.8 ft. dist. marked,

T1S R36E S34 BT

A Pine 14 ins. diam. bears S45°E 81.6 ft. dist. marked,

T2S R36E S3 BT

A Pine 7 ins. diam. bears S70°W 40.5 ft. dist. marked,


T2s R36 E S4 BT

A Fir 18 ins. diam. bears N10°W 115.6 ft. dist. marked, T1S R36E S33BT

All distances taken to a brass washer in the blaze of each tree.

Set a steel fence post approx. 6 ft. west of corner with Forest Boundary sign attached.

Used a steel tape & magnetic compass with declination equal 20° East.



REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1859 DOUGLAS M. FERGUSON 848

Office of Surveyor County of Wasatch
State of Utah, I hereby certify that the within instrument was filed in this office for record on the 10th day of August, 1972, at 10 o'clock am, (signed) Douglas M. Ferguson by Douglas M. Ferguson (DEPUTY)