

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 03/14/23.

CORNER DESIGNATION: A-1, the Northwest corner of Section 6, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. The corner was recovered, (a stone 18”X16”X10”), 26” below road was recovered by Otis Gould, U.S Department of the Interior Surveyor in 1940. Gould established a 3’ long by 3” diameter witness corner monument, 28 lks. East of corner point. The stone corner was replaced by a brass cap monument on Survey No. S-156-C. The brass cap corner monument was recovered and accessory tags were placed on Corner Record No. 03-49-G. The brass cap corner monument was recovered in 2005, referenced, and replaced with a rebar with 2” aluminum cap after road construction. All subsequent surveys in the area, since the Gould recovery have held this corner perpetuated by Gould.

MONUMENT AND ACCESSORIES FOUND: Found 2” aluminum cap on 5/8” rebar at surface of road and a 3” brass cap witness monument to the East. The corner monument cap is stamped as shown in Monument Marking Detail. The brass cap witness monument is stamped as shown below.

MONUMENT MARKING DETAIL:

	T4N	WC	
	S36 S31	28 E	
shown.	-----	S31 S36	The existing witness brass cap is mismarked as shown
	S1 S6	-----	
	T3N	S1 S6	
	PLS 2627	R27E R28E	
		T3N	
		1940	

MAINTAINED CORNER MONUMENT:

New accessories:

The existing 3” brass cap witness corner bears N 89°34’08” E, 18.84’ Attached bearing object tag to railroad tie post 2’ East of witness mōnument.

A 5/8”X24” rebar with blue plastic cap marked “Wells Surveying 54657PLS” bears S 27°39’05” E, 46.87’. Wired bearing object sign to rebar.

A 5/8”X24” rebar with blue plastic cap marked “Wells Surveying 54657PLS” bears S 15°10’42” E, 89.38’. Wired bearing object sign to rebar.

A 5/8”X24” rebar with blue plastic cap marked “Wells Surveying 54657PLS” bears N 32°41’43” W, 53.77’. Wired bearing object sign to railroad tie post 6” North of rebar.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: Corner monument is located in Cornel Jordan Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 771591.87

E: 8489766.86

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\3N28A-1



RENEWS: 6:30!24

24-004-C