

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/21/23.

CORNER DESIGNATION: E-19, the North Quarter Corner of Section 11, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. The corner was reestablished on Survey No. 258, found in Record of Private Survey Books. A 2”X10”X9” stone was set for the corner on that survey.

MONUMENT AND ACCESSORIES FOUND: Found and held straight part a 60 penny nail 6” below the road surface of Emert Road.

MONUMENT MARKING DETAIL:

T3N R28E
S2
1/4 -----
S11
2023
PLS 54657

NEW MONUMENT SET:

At the position of the found nail, set a 5/8”X18” rebar 24” in the ground to refusal and capped with a 2” aluminum cap. I poured concrete around the rebar. The aluminum cap is 8” below road surface and is marked as shown in the Monument Marking Detail.

New accessories:

A 5/8”X24” rebar with blue plastic cap marked “Wells Surveying 54657PLS” bears N 33°43’23” E, 32.03’, in East-West fence line, 6” South of a railroad tie post. Nailed Witness post and bearing object signs to railroad tie post.

A 5/8”X24” rebar with blue plastic cap marked “Wells Surveying 54657PLS” bears S 77°50’49” E, 86.26’, by a large rock at edge of driveway. Wired bearing object sign to rebar.

A 5/8”X24” rebar with blue plastic cap marked “Wells Surveying 54657PLS” bears S 45°02’35” W, 48.32’, 6” North of railroad tie fence angle post. Nailed bearing object sign to the railroad tie post.

A 5/8”X24” rebar with blue plastic cap marked “Wells Surveying 54657PLS” bears N 62°19’18” W, 52.33’, 6” South of railroad tie post in East-West fence line, . Nailed bearing object sign to the railroad tie post.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: The corner monument is located in Emert Road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 766345.13
E: 8513515.68

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

Surveyor's Seal

\3N28E-19



RENEWS: 6:30:24

24-004-C