

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 04/04/23.

CORNER DESIGNATION: E-7, the South Quarter corner of Section 5, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. Survey Number 408, found in Record of Private Survey Books, reestablished the corner and set a stone marked "1/4" with a brick underneath. Survey No. S-14-B computed the corner location after recovering the East 1/16th corner, (2" pipe and stone), established on Survey No. 408. Note: The East 1/16th corner area is now covered with 4 to 6' of road fill from an access road off Highway 207.

MONUMENT AND ACCESSORIES FOUND: None. This corner was reestablished on the parallel of latitude, by single proportion measure between the computed position for the East 1/16th corner and Southwest corner of Section 5. The corner falls approximately 2' North of an existing East-West fence line.

MONUMENT MARKING DETAIL:

T3N R28E  
S5  
1/4 -----  
S8  
2023  
PLS 54657

NEW MONUMENT SET:

At the position established by survey, set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe 30" in the ground. Attached Witness post sign to railroad tie fence post 4' West of corner monument. The brass cap is stamped as shown in Monument Marking Detail.

New accessories:

- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 88°39'13" E, 42.50', in East-West fence line. Wired bearing object sign to rebar.
- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 85°21'39" E, 17.16', 6" South of Wood fence post. Nailed bearing object sign to wood fence post.
- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 85°48'11" W, 25.62', 6" South of wood fence post. Nailed bearing object sign to wood fence post.
- A 5/8"X24" rebar with blue plastic cap marked "Wells Surveying 54657PLS" bears S 87°53'25" W, 55.15', in East-West fence line. Wired bearing object sign to rebar.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: Corner is located just North of an East-West fence line, near a road South of the East-West fence line.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 766293.66  
E: 8497589.49

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\3N28E-7



RENEWS: 6:30:24

24-004-C