

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 04/25/23.

CORNER DESIGNATION: J-11, the South Quarter Corner of Section 9, Township 3 North, Range 28 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by N.H. Gates under Contract No. 84, dated July 22, 1859. Gates set a post in earth mound. Survey No. 357, found in Record of Private Survey Books, shows a symbol for the corner which indicates the corner was once marked with a square wood post set 18" in the ground.

MONUMENT AND ACCESSORIES FOUND: None. I reestablished the corner point by single proportion measure between the Southwest and Southeast corners of Section 9, on the parallel of latitude.

MONUMENT MARKING DETAIL:

T3N R28E  
S9  
1/4 -----  
S16  
2023  
PLS 54657

NEW MONUMENT SET:

At the position determined by survey set a 2 1/2" brass cap on 1 1/4" by 30" galvanized iron pipe with cap 20" below ground line in previously farmed field. The brass cap is marked as shown in Monument Marking Detail. The corner is located about 25' East of the centerline of a North-South field road. Set a steel fence post 1' West of corner monument with witness sign facing the road.

New accessories:

A Silver Deep-1 magnet buried 22" below ground line bears N 40°46'16" E, 29.46'. Buried bearing object sign with the Deep-1 magnet.

A Pink Deep-1 magnet buried 22" below ground line bears S 46°04'50" E, 27.97'. Buried bearing object sign with the Deep-1 magnet.

A Blue Deep-1 magnet buried 22" below ground line bears S 54°42'10" W, 51.88'. Buried bearing object sign with the Deep-1 magnet.

A Orange Deep-1 magnet buried 22" below ground line bears N 60°57'21" W, 48.67'. Buried bearing object sign with the Deep-1 magnet.

Courses to corner accessories are State Plane Grid bearings and distances.

LOCATION AND COMMENTS: The corner falls in a previously farmed field about 25' East of a North-South field road.

OREGON STATE PLANE COORDINATE, North Zone NAD 83(91), International Feet Units:

N: 760995.26  
E: 8503021.73

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

\3N28J-11



RENEWS: 6! 30:24

24-004-C