

**OREGON CORNER RESTORATION FORM**

Section 1 Township 3N Range 29E  
County Umatilla Date: 08/20/10

Corner Designation: 3N29C25

1/4 Corner common to section 11, T3NR29E, and section 6, T3NR30E.

Condition Report Only  
 Not Found  
 Remonumented  
 Unrecorded  
 Surveyed In  
 Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by David P. Thompson in 1859. He set a post in a mound of earth.

**Monuments and Accessories Found: (Condition and Source)**

None

**Diagram**



Orange Magnet ●

**Sketch**

Silver Magnet ●

○ 18" Deep  
BC

Blue Magnet ●

● Pink Magnet

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N769863.29  
E8553701.33

LAT - 45° 46' 12.30132" N  
LON - 119° 07' 19.52064" W

**Monument (s) Set (Procedures and Description)**

Set a 1"x30" flared galvanized iron pipe with a 2 1/2" brass cap, 18" below surface, by single proportionate method.

**References Set:** "Deep One" magnets by Berntsen.  
An Orange magnet, 20" deep, lies N 29°00' W, 15.81'.  
A Silver magnet, 20" deep, lies N 55°00' E, 17.17'.  
A Pink magnet, 20" deep, lies S 47°00' E, 14.25'.  
A Blue magnet, 20" deep, lies S 63°30' W, 17.55'.

**Location and Comments**

Corner is in an active wheat field  
approx 1/2 mi. S of Stage Gulch road.  
N of I-84.

**Compass Declination**  
17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 1-11  
Rec'd By: KK  
No. 11-08-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/11