

**OREGON CORNER RESTORATION FORM**

Section 9  
County Umatilla

Township 3N  
Date: 09/08/09

Range 29E

Corner Designation: 3N29J13

Corner common to sections 9,10,15 and 16, T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by N.H. Gates in 1859. He set a post in a mound of earth w/ charcoal.  
Staebler set a Brass Cap at position of found charred stake in survey H-4-B.  
D. Haddock found the Brass Cap set by Staebler.

**Monuments and Accessories Found: (Condition and Source)**

- A 2.5" B.C.
- A <sup>8</sup>/<sub>8</sub>" Iron rebar w/rpc #852 under the fence lies N 89° 30' W, 71.00'.
- A <sup>8</sup>/<sub>8</sub>" Iron rebar w/rpc #852 under the fence lies S 00°45' E, 61.77'.
- A <sup>8</sup>/<sub>8</sub>" Iron rebar w/rpc #852 under the fence lies S 01°45' E, 32.04'.
- A <sup>8</sup>/<sub>8</sub>" Iron rebar w/rpc #852 under the fence lies N 89°00' W, 35.48'.

**Diagram**



**Sketch**



NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N761555.42  
E8538057.72

LAT - 45° 44' 52.86016" N  
LON - 119° 11' 02.08694" W

**Monument (s) Set (Procedures and Description)**

None.

**References Set:**

None.

**Location and Comments**

The corner is located at the Northeast fence corner of the Echo Hills Golf Course.

**Compass Declination**  
17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 41, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

RENEWAL DATE: 12/31/09

**RECEIVED BY:**

Date: 10-09  
Rec'd By: KE  
No. 09-146R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055