

OREGON CORNER RESTORATION FORM

Section 15,14 Township 3N
County Umatilla Date: 05/03/10

Range 29E

Corner Designation: 3N29L17

Corner common to sections 14,15 T3NR29E.

Condition Report Only
 Not Found
 Remonumented
 Unrecorded
 Surveyed In
 Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.


Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch



NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N759030.72
E8543371.19

LAT - 45° 44' 27.07612" N
LON - 119° 09' 47.75534" W

Monument (s) Set (Procedures and Description)

A 1 1/2" x 30" Galvanized iron pipe w/ a 2 1/2" Brass capped monument 20" below the surface, stamped as shown above. Set by single proportion. Corner position is inside the radius of an irrigated center pivot, and appears to be just North of an electrical or water main line. The magnets to the South are in the edge of a recent excavation or maintenance activity.

References Set: Deep One magnets by Berntsen.

- An Orange magnet 24" deep lies N 49°20' W, 17.51'.
- A Silver magnet 24" deep lies N 50°15' E, 18.41'.
- A Pink magnet 24" deep lies S 51°40' E, 15.53'.
- A Blue magnet 24" deep lies S 48°30' W, 17.13'.

Location and Comments

The corner is 0.5 miles South from the intersection of HWY. 320 and Coppinger Road, and West 2.0 miles.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 5-10
Rec'd By: KE
No. 10-78-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11