

OREGON CORNER RESTORATION FORM

Section 16,17,20,21 Township 3N
County Umatilla Date: 02/17/10

Range 29E

Corner Designation: 3N29N9

Corner common to sections 16,17,20 and 21, T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by N.H. Gates in 1859. He set a post in a mound of earth.
Staebler set a 1 x 30" iron pipe w/ 2 1/2" B.C. on survey I-158-B.

Monuments and Accessories Found: (Condition and Source)

A 2 1/2" Brass Cap, as stamped below.

Diagram



Sketch

- Orange Magnet
- Silver Magnet
- 2 1/2" B.C.
21" Deep
- Blue Magnet
- Pink Magnet

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N756127.54
E8532809.06

LAT - 45° 44' 00.12029" N
LON - 119° 12' 17.32806" W

Monument (s) Set (Procedures and Description)

None.

References Set: "Deep One" magnets by Bernsten.

- An Orange magnet 18" deep lies N 29°10' W, 17.59'.
- A Silver magnet 18" deep lies N 39°30' E, 18.14'.
- A Pink magnet 18" deep lies S 23°40' E, 18.33'.
- A Blue magnet 18" deep lies S 46°00' W, 17.72'.

Location and Comments

Corner is in the N. edge of a center pivot field, S. of an irrigation canal, SW of Echo, and due S. of Dick Snow's ranch house.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: RE
No. 11-14-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11