

2

RTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 29E., W.M.

Corner Code No. P-21


Notes: Monument marked as shown below

History of original corner establishment:

This corner was originally established by N. H. Gates, Deputy Surveyor, under Contract No. 84, dated July 22, 1859.

The original notes state:

"Set post for 1/4 Sec corner in mound of Earth & @ as per instructions"



P-21

Corner No.
Compass Declination: 18.0°

Description of corner evidence found:

Long standing North-South fence line. After surveying to remonumented Section corner locations North and South of the corner point, I re-establish this corner mid-way between the Northwest and Southwest corners of Section 24, using the existing North-South fence line to control corner location in the longitudinal dimension.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" Brass cap on a 1 1/4" by 30" G.I.P. 24" in ground and surrounded with a mound of earth from which:

A 5/8" by 30" rebar bears North 46.05' capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106". Nailed bearing object sign on wood fence post just North of rebar.

A 5/8" by 30" rebar bears S 66° E - 104.10', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106". Nailed bearing object sign on wood fence post just West of rebar.

A washer stamped "W.R. WELLS, PLS 1106" bears S 0 1/2° E - 28.60'. Washer is nailed 6" above ground on West side of a 8" by 8" railroad tie.

A 5/8" by 30" rebar bears S 00° 08' 13" W - 792.00 feet.

Set a steel fence post 3.3' North of monument with a Witness Corner sign attached.

Corner is located in a North-South fenceline, 50' North of a East-West road approaching from East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 6-9-72

Rec'd By KF

No. 92-65-C

☆ GPO—798-276