

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 3N, R 29E . , W.M.

Corner Code No. R-21


Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by N. H. Gates, Deputy Surveyor, under Contract No. 64, dated July 22, 1897.

The original notes state:

\*Set post for corner to Secs 23, 24, 25 & 26 in mound of Earth & 8 as per instructions



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Fence corner with fences extending to the North and West. After verifying corner location by survey, I accept this fence corner as the best remaining evidence of the original corner location and remonument the corner point as indicated below.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2 1/2" Brass cap on a 1 1/4" by 30" G.I.P. 24" in ground and surrounded with a mound of earth from which:

A 5/8" by 30" rebar bears N 1°E - 28.1', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106". Set a steel fence post by rebar with a Bearing Object sign attached.

A brass washer bears N 14 1/2°E - 230.7'. Washer is stamped "W.R. WELLS, PLS 1106" and is nailed 1' above ground on East side of BPA pole # 18-7-B. Nailed Bearing Object sign on pole.

A 5/8" by 30" rebar bears West 24.9', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106". Set a steel fence post by rebar with a Bearing Object sign attached.

A 5/8" by 30" rebar bears S 89 1/2°W - 55.5', capped with a yellow plastic cap marked "W.R. WELLS, PLS 1106". Rebar is at the base of a wood fence post with a Bearing Object sign attached.

Corner falls at fence corner with fences North and West. Nailed Witness Corner sign to 8" by 8" railroad tie fence corner by monument.

|   |
|---|
| REGISTERED<br>PROFESSIONAL<br>LAND SURVEYOR         |
| <i>Will R. Wells</i>                                |
| OREGON<br>JULY 22, 1977<br>WILLIAM R. WELLS<br>1106 |

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Umatilla County Surveyor  
Date 6-92  
Rec'd By KK  
No. 92-65-C

☆ GPO-798-276