

**OREGON CORNER RESTORATION FORM**

Section 19,20,29,30 Township 3N  
County Umatilla Date: 03/08/10

Range 29E

Corner Designation: 3N29R5

Corner common to sections 19,20,29,30 T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by Gates. He set a post in a mound of earth in 1860.  
Stebler set a 2 1/2" Brass cap in 1974, Survey #I-158-B.  
Edwards found Brass capped monument badly bent, 91-92-R.


**Monuments and Accessories Found: (Condition and Source)**

Found Brass cap with bent Iron pipe as called by Edwards. Top half was badly bent out of position.

Diagram



Sketch



NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N750739.16  
E8527596.56

LAT - 45° 43' 07.74112211" N  
LON - 119° 13' 31.99836177" W

**Monument (s) Set (Procedures and Description)**

Set a 1 1/8" x 30" Galvanized iron pipe with a 2 1/2" Brass cap, stamped as shown above, in place of the found bent monument. Monument is 18" below surface.

**References Set:** "Deep One" magnets by Bernsten.

- An Orange magnet, 18" deep lies N 39°15' W, 18.23'.
- A Silver magnet, 18" deep lies N 65° E, 20.22'.
- A Pink magnet, 18" deep lies S 32°20' E, 27.08'.
- A Blue magnet, 18" deep lies S 40°30' W, 23.37'.

**Location and Comments**

The corner is 1.2 miles South of the intersection of Hwy. 320 and Snow Road, and West 0.5 miles from the Ag. Runway.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert Douglas English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 3-10  
Rec'd By: KK  
No. 10-37-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/11