

OREGON CORNER RESTORATION FORM

Section 29 Township 3N
County Umatilla Date: 02/17/10

Range 29E

Corner Designation: 3N29R9

Corner common to sections 20,21,28 and 29, T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by N.H. Gates in 1859. He set a post in a mound of earth.
Staebler set a 1 x 30" iron pipe w/ 2 1/2" B.C. on survey I-158-B.

Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch

• Orange Magnet

• Silver Magnet

○ 2 1/2" B.C.
18" Deep

• Blue Magnet

• Pink Magnet

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N750800.17
E8532912.44

LAT - 45° 43' 07.51358" N
LON - 119° 12' 17.07491" W

Monument (s) Set (Procedures and Description)

A 1"x30" galvanized iron pipe with a 2 1/2" brass cap, 18" below surface, near an irrigation pivot.
Stamped as shown above.
Reset corner from referenced ties to Staebler's survey.

References Set: "Deep One" magnets by Bernsten.

- An Orange magnet 20" deep lies N 58°00' W, 17.02'.
- A Blue magnet 20" deep lies S32 °20' W, 13.18'.
- A Silver magnet 20" deep lies N 44°00' E, 18.26'.
- A Pink magnet 20" deep lies S 64°30' E, 16.61'.

Location and Comments

The corner is .5 miles West of the intersection of Hwy 320 and Snow Road, North of the House in a field.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: KK
No. 11-17-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11