

**OREGON CORNER RESTORATION FORM**

Section 27,28,33,34

Township 3N

Range 29E

County Umatilla

Date: 8/06/10

Corner Designation: 3N29V13

Section corner common to T3NR29E sections 27,28,33, and 34.

_____	Condition Report Only
<input checked="" type="checkbox"/>	Not Found
<input checked="" type="checkbox"/>	Re-monumented
_____	Unrecorded
<input checked="" type="checkbox"/>	Surveyed In
<input checked="" type="checkbox"/>	Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by Gates in 1859. He set a post in a mound of earth.

**Monuments and Accessories Found: (Condition and Source)**

None.

**Diagram**



**Sketch**



Orange magnet 22" Deep

Silver magnet 23" Deep

○ B.C. Monument

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

Blue magnet 21" Deep

Pink magnet 22" Deep

N742980.19  
E8538342.98

LAT - 45° 41' 49.445308" N  
LON - 119° 11' 02.331364" W

**Monument (s) Set (Procedures and Description)**

1 1/4" x 30" galvanized iron pipe w/ a 2 1/2" Brass cap, stamped as shown above. Set by double proportionate method. Any evidence of the corner has been long farmed out.

**References Set:** Deep One magnets by Berntsen.

An Orange magnet lies N 67° W, 16.33'.

A Silver magnet lies N 27°20' E, 15.52'.

A Pink magnet lies S 50° E, 14.17'.

A Blue magnet lies S 26°10' W, 16.55'.

**Location and Comments**

The corner falls in a active farm field just S of a small draw and approx 125 yd. E of farm road.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY II, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

**Firm / Agency**

Date: 8-10  
Rec'd By: KE  
No. 10-147-B

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/11