

OREGON CORNER RESTORATION FORM

Section 27,28,33,34

Township 3N

Range 29E

County Umatilla

Date: 8/06/10

Corner Designation: 3N29V13

Section corner common to T3NR29E sections 27,28,33, and 34.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates in 1859. He set a post in a mound of earth.

Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch

Orange magnet 22" Deep

Silver magnet 23" Deep

○ B.C. Monument

Blue magnet 21" Deep

Pink magnet 22" Deep

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N745636.39
E8538314.27

LAT - 45° 42' 15.67613" N
LON - 119° 11' 02.13308" W

Monument (s) Set (Procedures and Description)

1 1/4" x 30" galvanized iron pipe w/ a 2 1/2" brass cap, stamped as shown above. Set by double proportionate method. Any evidence of the corner has been long farmed out.

References Set: "Deep One" magnets by Berntsen.

An Orange magnet lies N 67° W, 16.33'.

A Silver magnet lies N 27°20' E, 15.52'.

A Pink magnet lies S 50° E, 14.17'.

A Blue magnet lies S 26°10' W, 16.55'.

Location and Comments

The corner falls in a active farm field just S of a small draw and approx 125 yd. E of farm road.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English

OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RENEWAL DATE: 12/31/11

RECEIVED BY:

Date: 1-11
Rec'd By: KE
No. 11-19-2

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055