

**OREGON CORNER RESTORATION FORM**

Section 28,29,32,33 Township 3N  
County Umatilla Date: 03/11/10

Range 29E

Corner Designation: 3N29V9

Corner common to sections 28,29,32,33 T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.  
Harris set a stone and a 1/2" Iron rebar in survey #Q-1655

**Monuments and Accessories Found: (Condition and Source)**

Found a Bureau of Reclamation Brass cap not of record, in a mound of stone.

Diagram



Sketch

2 1/2" BC

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N745543.22  
E8533015.61

LAT - 45° 42' 15.59696518" N  
LON - 119° 12' 16.80207117" W

**Monument (s) Set (Procedures and Description)**

None.

**References Set:** "Deep One" magnets by Berntsen.

An Orange magnet, 18" deep, lies N 44° W, 13.30'.

A Blue magnet, 18" deep, lies N 42° E, 12.58'.

A Pink magnet, 18" deep, lies S 35° E, 13.57'.

A Silver magnet, 18" deep, lies S 37° W, 12.86'.

**Location and Comments**

The corner is South 2.2 miles South of the intersection of Snow Road and Hwy. 320., and East 0.5 miles in a field.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 3-10  
Rec'd By: KK  
No. 10-47-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/11