

**OREGON CORNER RESTORATION FORM**

Section 34,35 Township 3N  
County Umatilla Date: 05/27/10

Range 29E

Corner Designation: 3N29X17

Corner common to sections 34,35 T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


**Previous Renewals / Surveys, etc.**

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.

**Monuments and Accessories Found: (Condition and Source)**

None.

**Diagram**



**Sketch**

Orange Magnet 18" Deep ●

Silver Magnet 18" Deep ●

○ Brass Cap 24" Deep

Blue Magnet 18" Deep ●

● Pink Magnet 18" Deep

NAD 83/91  
OREGON STATE PLANE NORTH  
INTERNATIONAL FEET

N743136.70  
E8543670.21

LAT - 45° 41' 50.12678" N  
LON - 119° 09' 47.24794" W

**Monument (s) Set (Procedures and Description)**

A 1 1/2" x 30" Galvanized iron pipe w/ a 2 1/2" Brass capped monument 24" below the surface, stamped as shown above. Set by single proportion.

**References Set: "Deep One" Magnets by Berntsen.**

An Orange magnet, 18" deep lies N 37°30' W, 18.40'.

A Silver magnet, 18" deep lies N 56°20' E, 15.46'.

A Pink magnet, 18" deep lies S 29° E, 14.44'.

A Blue magnet, 18" deep lies S 56°10' W, 15.84'.

**Location and Comments**

Corner is in the middle of a dryland wheat field, approximately 1 -1/2 mile SE from the Road on the South edge of Lloyd Piercy's Vineyard.

**Compass Declination**

17° E

**Surveyors Seal**

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Robert D. English*  
OREGON  
JANUARY 11, 2005  
ROBERT DOUGLAS ENGLISH  
43406LS

**RECEIVED BY:**

Date: 6-10  
Rec'd By: KK  
No. 10-103-R

**Firm / Agency**

Survey One, LLC.  
P.O. Box 382  
Pendleton, OR 97801  
(541) 276-2055

RENEWAL DATE: 12/31/11