

OREGON CORNER RESTORATION FORM

Section 34,35 Township 3N
County Umatilla Date: 05/27/10

Range 29E

Corner Designation: 3N29X17

Corner common to sections 34,35 T3NR29E.

- Condition Report Only
- Not Found
- Remonumented
- Unrecorded
- Surveyed In
- Referenced Out


Previous Renewals / Surveys, etc.

Originally Surveyed by Gates. He set a post in a mound of earth in 1859.

Monuments and Accessories Found: (Condition and Source)

None.

Diagram



Sketch

Orange Magnet 18" Deep ●

Silver Magnet 18" Deep ●

○ Brass Cap 24" Deep

Blue Magnet 18" Deep ●

● Pink Magnet 18" Deep

NAD 83/91
OREGON STATE PLANE NORTH
INTERNATIONAL FEET

N743131.87
E8543675.53

LAT - 45° 41' 50.08305" N
LON - 119° 09' 47.18095" W

Monument (s) Set (Procedures and Description)

A 1 1/2" x 30" galvanized iron pipe w/ a 2 1/2" brass cap, 24" below the surface, stamped as shown above. Set by single proportionate method.

References Set: "Deep One" Magnets by Berntsen.

An Orange magnet, 18" deep lies N 37°30' W, 18.40'.

A Silver magnet, 18" deep lies N 56°20' E, 15.46'.

A Pink magnet, 18" deep lies S 29° E, 14.44'.

A Blue magnet, 18" deep lies S 56°10' W, 15.84'.

Location and Comments

Corner is in the middle of a dryland wheat field, approximately 1 -1/2 mile SE from the Road on the South edge of Lloyd Piercy's Vineyard.

Compass Declination

17° E

Surveyors Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
43406LS

RECEIVED BY:

Date: 1-11
Rec'd By: KE
No. 11-20-R

Firm / Agency

Survey One, LLC.
P.O. Box 382
Pendleton, OR 97801
(541) 276-2055

RENEWAL DATE: 12/31/11