

CORNER RESTORATION FORM

Township 3N Range 30E Section 1,2,11&12 County UMATILLA

State OREGON Date 4-7-2015 Number E-21

Corner Designation : SECTION 1, 2, 11 & 12

Previous Renewals ORIGINAL SOURCE OF CORNER

UNDER GLO CONTRACT #95 BY W. CAMPBELL DATED
SEPTEMBER 19, 1860 SET POST

Accessories Found:
NONE


BASIS OF BEARINGS, NAD 83/91 OREGON STATE PLANE COORDINATES NORTH ZONE:

NORTHING: 767560.885
EASTING: 8580761.101

- Condition Report Only
- Not Found
- Renewed
- Surveyed In
- Referenced

MONUMENT DETAIL

Found Set



Monument & Accessories Set (Procedure and Description)

- SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 0.2' ABOVE GRADE SOUTH SIDE OF RAILROAD TIE POST SURVEY MARKER SIGN ON THE RAILROAD TIE POST.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, BEARING OBJECT SIGN ON T-POST, N84°38'E 20.27'.
- SET 5/8" REBAR & CAP PLS 61420 1' BELOW GRADE, S20°34'W 15.15'.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE, N88°03'W 112.45'.
- SET 5/8" REBAR & CAP PLS 61420 AT GRADE, BEARING OBJECT SIGN ON T-POST, N3°32'W 36.27'.

Sketch of Monument, Accessories and General Area

The sketch shows a central point with several lines extending to other markers. The markers are:

- Top: SET 5/8" REBAR & CAP PLS 61420 AT GRADE, BEARING OBJECT SIGN ON T-POST. Bearing: N3°32'W, Distance: 36.27'.
- Right: SET 5/8" REBAR & CAP PLS 61420 AT GRADE, BEARING OBJECT SIGN ON T-POST. Bearing: N84°38'E, Distance: 20.27'.
- Bottom: SET 2 1/2" BRASS CAP ON 1 1/4"x30" PIPE 0.2' ABOVE GRADE ON THE SOUTH SIDE OF RAILROAD TIE POST SURVEY MARKER SIGN ON THE RAILROAD TIE POST.
- Bottom-Left: SET 5/8" REBAR & CAP PLS 61420 1' BELOW GRADE. Bearing: S20°34'W, Distance: 15.15'.
- Left: SET 5/8" REBAR & CAP PLS 61420 AT GRADE IN FENCE LINE. Bearing: N88°03'W, Distance: 112.45'.

Other features include 'ELECTRIC FENCE' lines and a 'FIELD' area. A north arrow is shown on the right.

REGISTERED PROFESSIONAL LAND SURVEYOR

Lance Clark King

OREGON
MAY 10, 2011
LANCE CLARK KING
61420

RENEWS: 6/30/2015

Agency:
CK3, LLC
945 W. ORCHARD
HERMISTON OREGON 97838
OFFICE: 541-567-2345
FAX: 541-567-2305
WEB: CK3LLC.NET
Field Book # 0-289

COUNTY SURVEYOR RECORDING INFO

Received *Mary Robert*

Filed 6/12/2015

Survey No. 15-050-C

Drawing No. C-853

Index No. E-21