

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 11/28/12

CORNER DESIGNATION: R-19, The South Quarter Corner of Section 23, Township 3 North, Range 30 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by William B. Campbell, Deputy Surveyor, under contract No. 95, dated September 19, 1860. Notes State: Set a post for quarter section corner, drove charred stake as per instructions. Umatilla County Record of Survey No. 06-452-B held a old fence post for the corner.

MONUMENT AND ACCESSORIES FOUND: Held the old fence post in rock barrel as reported on Umatilla County Record of Survey No. 06-452-B.

MONUMENT MARKING DETAIL:

WC
5.00 FT
T3N R30E
1 S23
4 S26
2012
PLS 54657

MONUMENT SET: A monument cannot be set at the true corner point because of the barrel full of rocks. Set a Witness Corner Monument on the South line of Section 23, South 89°47'05" West, 5.00 feet from the true corner point. Set a 2 3/8" dia. brass cap on a 1 1/4"x30" galvanized iron pipe 20" in the ground to bedrock. Surrounded monument with a 3 foot diameter mound of stones and earth. Monument marked as shown in "Monument Marking Detail".

From which:

A 5/8"x24" iron rebar with 1 1/4" purple plastic cap marked "Wells Surveying PLS 54657" 3" above ground level bears North 50 1/2° East, 36.2 feet.

A 5/8"x24" iron rebar with 1 1/4" purple plastic cap marked "Wells Surveying PLS 54657" 1" above ground level bears South 22 1/2° East, 21.6 feet.

A 5/8"x24" iron rebar with 1 1/4" purple plastic cap marked "Wells Surveying PLS 54657" 1" above ground level bears South 60° West, 34.5 feet.

A 5/8"x24" iron rebar with 1 1/4" purple plastic cap marked "Wells Surveying PLS 54657" 5" above ground level on the South Bank of Rohde Road bears North 23° West, 53.1 feet.

Wired bearing object signs to all rebars.

LOCATION AND COMMENTS: Corner is located in a non farmed scab area approximately 30' feet South of Rohde Road.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

/3N30R19


RECEIVED BY

Umatilla County Surveyor

Date: 12-6/12

Rec'd By: S. Oles

No.: 12-154-B



RENEWS: 6-30-14