

### OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 08/18/09

CORNER DESIGNATION: A-17, The Northwest Corner of Section 2, Township 2 North, Range 30 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by David P. Thompson Deputy Surveyor under his contract dated July 22, 1859. Notes state: Set post for corner to sections 2, 3, 34, and 35 in mound of earth as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Held a railroad tie fence corner at the intersection of a fence lines extending East, West and South as the best remaining evidence of the original corner location. Ralph Thompson, in his Survey No. D-13-B, calls for a found 7" by 8" by 18" stone with four notches. We found a pile of loose stones at the fence corner and one stone of approximate size called for by Ralph Thompson, but found no definite notches. We searched for the nearest five 1/2" rebars called on Survey No. D-13-B, but only found 1 undisturbed rebar and 1 badly bent rebar. The found undisturbed rebar indicates we monumented nearly the same position for the corner as Ralph Thompson used.

MONUMENT MARKING DETAIL:

T3N R30E  
S34|S35  
S3|S2  
T2N  
2009  
PLS 1106

MONUMENT SET: Set a 2 3/8" dia. brass cap on a 1 1/4"x30" galvanized iron pipe with top 4" above ground level in small mound of stone. Monument is located on the North side of a railroad tie fence post. Cap is marked as shown in "Monument Marking Detail".

New accessories:

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" bears South 88° East, 33.4 feet.

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" bears South 01° East, 43.5 feet.

A 5/8"x24" dia. iron rebar with 1 1/4" red plastic cap marked "ORPLS 1106 WAPLS 17372" bears North 88° West, 38.6 feet.

A 3/4" brass washer stamped "PLS 1106" attached to railroad tie fence post 6" above ground level bears South 63° East, 0.60 feet.

Attached witness post sign to railroad tie with brass washer. Attached bearing object signs to all iron rebar and railroad tie with brass washer.

LOCATION AND COMMENTS: Corner is located 4" above ground level in a small mound of stone on the North side of a railroad tie fence post at the intersection of fence lines extending East, West and South.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Eddie Kilner

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

V2N30A17

RECEIVED BY  
Umatilla County Surveyors  
Date 12/09  
Rec'd by JR  
No. 09-172-C

renews 6-30-10