

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/1/15.

CORNER DESIGNATION: The North One-Quarter Corner of Section 5, Township 3 North, Range 31 East, A-7.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec post.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T4N R31E  
1 S32  
4 S5  
T3N  
2015  
PLS 54657

MONUMENT SET:

Held fence corner with fences East, West and South. At a point just East of fence corner post, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap 2" above ground level, 10" East of fence corner post, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, 20" below ground level, bears North 30° East, 32.9 feet.
- A pink deep-1 magnet, 20" below ground level, bears South 37° East, 29.7 feet.
- A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level, in a fence post, bears South 04° West, 40.6 feet.
- A blue deep-1 magnet, 20" below ground level, bears South 45° West, 29.0 feet.

Buried bearing object tags with magnets. Nailed bearing object tag to fence post at brass washer. Wired witness post sign to fence post 10' West of corner.

LOCATION AND COMMENTS: At old fence corner post with fences West, East, and South.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 773221.95  
E = 8594064.15

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

Dean Roy

/3N31A7



15-052-c

RENEWS: 6-30-16