

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 3/26/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 4, Township 3 North, Range 31 East, C-9.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E  
1/4  
S5|S4  
2015  
PLS 54657

MONUMENT SET:

Held old fence corner post with fences North, East and West as best remaining evidence of original corner. At a point 1 foot North of old fence corner post, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with top 2" above ground level stamped as shown in "Monument Marking Detail".

From which:

- A 3/4" brash washer stamped "PLS 1106", 1 foot above ground level in fence gate post bears North 04° East, 65.9 feet.
- A 3/4" brass washer stamped "PLS 1106", 1 foot above ground level, bears South 84° East, 49.9 feet.
- A pink deep-1 magnet buried 20" in the ground, bears South 30° East, 30.3 feet.
- An orange deep-1 magnet buried 20" in the ground, in fence gate post, bears North 29° West, 26.0 feet.

Nailed bearing object tags to posts with brass washers. Buried bearing object tags with magnets. Attached witness sign to fence corner post, 1 foot South of monument.

LOCATION AND COMMENTS: At old fence corner post with fences North, East and West.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 770605.43  
E = 8596713.53

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS  
Dean Roy

/3N31C9



15-052-c

RENEWS: 6-30-16