

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/2/15

CORNER DESIGNATION: The Northwest Corner of Section 12, Township 3 North, Range 31 East, E-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instructions for corner to secs 1, 2, 11 & 12.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
S2|S1
S11|S12
2015
PLS 54657

MONUMENT SET:

Held intersect of field berms North and East as best remaining evidence of original corner location. At re-established corner position, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with top 20" below ground level, marked as shown in "Monument Marking Detail".

From which:

A silver deep-1 magnet, buried 20" in the ground, bears North 38° East, 28.8 feet.

A pink deep-1 magnet, buried 20" in the ground, bears South 61° East, 31.8 feet.

A blue deep-1 magnet, buried 20" in the ground, bears South 20° West, 33.0 feet.

An orange deep-1 magnet, buried 20" in the ground, bears North 51° West, 34.5 feet.

Buried bearing object tags with magnets. Set steel fence post with witness sign 1 foot North of monument.

LOCATION AND COMMENTS: At the intersection of field berms North and East, in CRP field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 768009.04

E = 8612616.48

FIRM: Wells Surveying

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, PLS

Dean Roy

/3N31E21



RENEWS: 6-30-16

15-052-C