

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 4/2/15

CORNER DESIGNATION: The West One-Quarter Corner of Section 12, Township 3 North, Range 31 East, G-21.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by D.S. Payne, under Contract No. 100, dated 8/1/1861, notes state: Set charred stake with mound trench and pits as per instrs. for 1/4 sec corner. John Kimbrell, in 1900 survey recorded in record of Private Survey Book 1, Page 424 and 425 recovered the "acknowledged 1/4 corner between Sections 10 and 11 but does not state what was recovered.

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T3N R31E
1/4
S11|S12
2015
PLS 54657

MONUMENT SET:

Re-established corner by single proportion measure between the Southwest and Northwest corner of Section 12 and set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, top 18" below ground level, stamped as shown in "Monument Marking Detail".

From which:

- A silver deep-1 magnet, buried 20" in the ground, bears North 51° East, 31.5 feet.
- A pink deep-1 magnet, buried 20" in the ground, bears South 41° East, 32.6 feet.
- A blue deep-1 magnet, buried 20" in the ground, bears South 49° West, 35.8 feet.
- An orange deep-1 magnet, buried 20" in the ground, bears North 52° West, 32.8 feet.

Buried bearing object tags with magnets. Set steel fence post with witness sign attached, 1 foot North of monument.

LOCATION AND COMMENTS: Corner falls in CRP field, 12 feet South of a newer, dim East-West field line. There are no location features such as field lines showing on the 1956 Farm Service Agency photos.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 765314.57
E = 8612670.31

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, PLS
Dean Roy

/3N31G21



RENEWALS: 6-30-16

15-052-C